

Eversource 2023 Level 3 ASO Study Customer Kickoff Meeting

Western Massachusetts & Greater Boston Areas

May 24, 2023

Outline

- Study Area and Project Overview
- Level 0 ASO Study Update
- Level 3 ASO Study Objectives
- Level 3 ASO Study Update
- Next Steps

Study Area and Project Lists

ASO Overview – Western Massachusetts

EVERSOURCE

Station Capacity (MW)	Level 0 - No Study	Level 0 - Transfer Limit Analysis	Level 3 - Transmission Study	Grand Total(MW)
PITTSFIELD AREA	0	0	22	22
AMHERST 17K			2	2
DOREEN 19A			9	9
FRENCH KING 21B			2	2
MONTAGUE 21C			5	5
PARTRIDGE 15E			4	4
SPRINGFIELD AREA	9	19	36	64
BLANDFORD 19J			29	29
BRECKWOOD 20A	4	2		6
CLINTON 21S		2		2
ORCHARD 27A		4		4
PIPER 21N	5	4		9
SILVER 30A		7		7
SOUTHWICK 29A			7	7
Grand Total	9	19	58	86

Number of Applications	Level 0 - No Study	Level 0 - Transfer Limit Analysis	Level 3 - Transmission Study	Grand Total
PITTSFIELD AREA	0	0	6	6
AMHERST 17K			1	1
DOREEN 19A			2	2
FRENCH KING 21B			1	1
MONTAGUE 21C			1	1
PARTRIDGE 15E			1	1
SPRINGFIELD AREA	2	7	9	18
BLANDFORD 19J			7	7
BRECKWOOD 20A	1	1		2
CLINTON 21S		1		1
ORCHARD 27A		2		2
PIPER 21N	1	1		2
SILVER 30A		2		2
SOUTHWICK 29A			2	2
Grand Total	2	7	15	24

- 12 substations impacted
- Level 0 - [No Study](#)
 - 9MW
 - 2 applications
- Level 0 - [Transfer Limit Analysis](#)
 - 19 MW
 - 7 applications
- Level 3 - [Transmission Study](#)
 - 58 MW
 - 15 applications


ASO Overview – Greater Boston

EVERSOURCE

Station Capacity (MW)	Level 0 - No Study	Level 0 - Transfer Limit Analysis	Level 3 - Transmission Study	Grand Total(MW)
Baker St 110	5			5
Canton 470			5	5
MAYNARD 416			5	5
MEDWAY 65			5	5
MYSTIC 250		8		8
NO. WOBURN 375		3		3
SEAFOOD WAY 99	2			2
SPEEN ST 433		10		10
Walpole 146			5	5
Grand Total	7	21	20	48

Number of Applications	Level 0 - No Study	Level 0 - Transfer Limit Analysis	Level 3 - Transmission Study	Grand Total
Baker St 110	1			1
Canton 470			1	1
MAYNARD 416			1	1
MEDWAY 65			1	1
MYSTIC 250		2		2
NO. WOBURN 375		2		2
SEAFOOD WAY 99	1			1
SPEEN ST 433		2		2
Walpole 146			1	1
Grand Total	2	6	4	12

- 8 substations impacted
- Level 0 - [No Study](#)
 - 7 MW
 - 2 applications
- Level 0 - [Transfer Limit Analysis](#)
 - 21 MW
 - 6 applications
- Level 3 - [Transmission Study](#)
 - 25 MW
 - 4 applications



Level 0 ASO Study Update

Level 0 ASO Study Update – WMA

- ES has successfully tested and validated technical data and PSCAD models for all Level 0 ASO Study participants by April 2023.
- Technical data and PSCAD model validation was performed in parallel with the transfer limit analysis to increase study efficiency.
- ES accommodated flexibility for the technical data and PSCAD model submission to the extent the overall study schedule was not impacted.
- Level 0 Transfer Limit Analysis (TLA) findings/results:
 - No thermal or voltage violations identified in the Level 0 Transfer Limit Analysis.
 - No application was moved from Level 0 to Level 3.
 - ISO-NE reviewed and approved the results of the Transfer Limit Analysis.
- Proposed Plan Applications (PPA) Submission and Approvals:
 - 2 projects totaling 8.55 MW with Level 0 No Study PPA level obtained PPA approval in the April and May Reliability Committee (RC) Meetings
 - 1 project totaling 2.231 MW with Level 0 TLA PPA level obtained PPA approval in the May RC Meeting
 - 6 projects totaling 17.13 MW with Level 0 TLA PPA level are expected to obtain PPA approval in the June RC Meeting
 - Level 0 PPA study to be completed on schedule and all PPA approvals for projects with acceptable models are expected in June.

Level 0 ASO Study Update – GB

- ES has successfully tested and validated technical data and PSCAD models for all Level 0 Study participants by April 2023.
- Technical data and PSCAD model validation was performed in parallel with the transfer limit analysis to increase study efficiency.
- ES accommodated flexibility for the technical data and PSCAD model submission to the extent the overall study schedule was not impacted.
- Level 0 Transfer Limit Analysis findings/results:
 - No thermal or voltage violations identified in the Level 0 Transfer Limit Analysis.
 - No application was moved from Level 0 to Level 3.
 - ISO-NE reviewed and approved the results of the Transfer Limit Analysis.
- Proposed Plan Applications (PPA) Submission and Approvals:
 - 2 projects totaling 8.3 MW with Level 0 TLA PPA level obtained PPA approval in the May RC Meeting
 - 4 projects totaling 13.2 MW with Level 0 TLA PPA level are expected to obtain PPA approval in the June RC Meeting
 - Level 0 PPA study completed on schedule and all PPA approvals for projects with acceptable models expected in June.

EVERSOURCE
ENERGY

Safety First and Always

EVERSOURCE
ENERGY

Safety First and Always

Level 3 ASO Study

Level 3 ASO Study Objective

- Steady-state analysis to assess thermal overloads and voltage limit violations resulting from the DER interconnections,
- Stability analysis to verify acceptable model performance and, to identify any violations of stability acceptability criteria following system disturbances resulting from the interconnection,
- Short-circuit analyses to assess if circuit breaker short-circuit capability limits are exceeded as a result of the interconnection;
- PSCAD evaluation to verify acceptable control stability and interactions between inverter-based technologies connected to Distribution and Transmission, and acceptable DER ride-through capabilities;
- Determine any upgrades that are required to eliminate any thermal or voltage violation, system dynamic and transient stability and, degradation to transfer capability.

EVERSOURCE

Next Steps

- Working with ISO-NE to develop Level 3 ASO study scopes
- Study assumptions have been finalized with ISO-NE
- Provide updates on preliminary study results after completion of the steady state and stability analyses
- Stay up to date with study schedule and progress updates via biweekly reports.

OPEN Q&A

Thank You!

Level 3 ASO Study Overview

- PSCAD Model Validation
 - Detailed technical data was requested from all Level 3 projects and is required to start studies
 - Collection and validation of PSCAD models for each project has been performed for all projects.
- Level 3 study
 - Study Assumptions and study scope of work will be finalized with ISO-NE.
 - Conduct thermal and voltage steady state, short circuit, stability and electromagnetic transient (EMT) analysis.
- Eversource will review each of the steady state, stability, short circuit and EMT results with ISO-NE before proceeding to the next stage of the study.
- ASO Study Participants will be informed if their project triggers a transmission system upgrade at the end of the steady state and stability analysis.
- ISO-NE will approve the proposed plan application (a.k.a I-39) after all studies have been completed.